



NOTES:

1. TO BE 12" MIN. OR AS RECOMMENDED BY HYDRANT MANUFACTURER.
2. COVER STONE WITH 8-MIL POLYETHYLENE BEFORE BACKFILLING.
3. CONCRETE COLLAR SHALL BE FLUSH WITH GROUND IN RURAL AREAS AND 8" BELOW FINISH GRADE IN RESIDENTIAL AREAS.
4. SET BURY LINE ON HYDRANT ASSEMBLY AT THE TOP CONCRETE COLLAR.

CITY OF NEW PHILADELPHIA

FIRE HYDRANT ASSEMBLY WITH VALVE AND VALVE BOX

STANDARD
CONSTRUCTION
DRAWING NO.

SD-133

REV. 11-2021